

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Township  
Kalamazoo  
(County)

Located in:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>12W.</u>	<u>C-10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

LIBER 2 PAGE 197  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 97 SEP 5 PM 3 42  
 CLERK - REGISTER  
*[Signature]*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Allen H. McMachen, in a field survey on July 25, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Robert Clark, Jr., D.S., Set quarter Section post, Bl. Ash 22" N. 50° W. 1 lk., Wh. Ash 10" S. 33° E. 9 lks.

1873 - Ed Strong, C.S., "Stone & Crockery, Stone by Chichester" (Strong's map shows meas. of 2658.15' to S.E. cor., Sec. 30).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in mon. box. Removed iron and box and dug to depth of 2' finding pointed stone standing on end surrounded with red brick and crockery. Point of stone is 0.4 feet South of surface iron location. Measured South 2660.94' to stone at S.E. corner, Section 30.

RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP

8/21/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone is accepted as a careful and faithful perpetuation of the position of the original corner. Removed stone and placed Harrison monument and monument box, Accessories:

- Nail & Tab in S.E. side U. Pole N. 45° E. 34.6'
- Nail & Tab in N.E. side, 10" Pine S. 50° E. 49.0'
- Nail & Tab in East side 24" Maple S. 30° W. 77.7'
- Nail & Tab in East side 30" Oak N. 20° W. 110.9'



Signed by Allen H. McMachen

Date 8/25/97

Surveyor's Michigan License No. 16935