

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Township  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>12W.</u>	<u>C-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1997 SEP 5 PM 3:42  
Clerk - Register  
*Jessie Johnson*

LIBER 2 PAGE 196

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on July 25, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Robert Clark, Jr., D.S., Set post corner to Sec. 29, 30, 31 & 32, Maple 18" S. 33° E. 42 lks., Hickory 8" S. 09° W. 31 lks.

1873 - Ed Strong, C.S., (Notes from Sec. 31) "Found stone by Chichester W.O. 30" N. 65° E. 42 lks. on the 5th day of Nov. 1873 and resurveyed and corrected a portion of the Section in accordance. The N.E. corner corrected 16 lks. to the East." (Strong's map shows distance of 2658.15' to E 1/4 cor., Sec. 30).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in mon. box. Removed box and iron and dug to depth of 2' finding a pointed stone with drill hole in virgin soil (Measured to stone at E 1/4 corner, Section 30 at 2660.94'). Stone was directly below surface iron and was too large to remove from hole. Rolled stone to North to allow placing entire Harrison Monument. Baseball size stones were found around corner stone.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
8/21/97 *R. 2.8*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone is accepted as a careful and faithful perpetuation of the position of the original corner. Moved stone to North and placed Harrison monument and monument box, Accessories:

- Nail & Tab in N.W. side 26" Oak N. 35° E. 44.9'
- Nail & Tab in West side, 14" Oak S. 30° E. 49.4'
- Nail & Tab in East side Twin 10" Ash S. 45° W. 42.9'
- Nail & Tab in N.E. side 16" Elm N. 70° W. 37.6'



Signed by *Allen H. McMachen*

Date 8/25/97

Surveyor's Michigan License No. 16935