

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'94 DEC 6 PM 3 55

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Alamo Township

1. Public Land Survey

T 1 S R 12 W

E-11

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. [Signature]

CLERK-REGISTER

LIBER

1 PG 1180

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: Robert Clark, U.S. Government Survey; Set Post Corner to Sections 28, 29, 32 & 33.

Wh. Oak 7" For Corner Post

1870: F. Hodgeman, County Surveyor; Section Corner tree standing.

Marked

Y. Oak 14" South 80° East 60 Lks

Wh. Oak 12" South 84° East 82 Lks

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7/21/94**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1964: Acro Engineering; Set 3/8" iron rod for Northeast Corner. Corner set from East 1/4 Post (found stone, from previous survey), and Northeast 1/8 Corner (found stone, from previous survey) measured from East 1/4 Post to Northeast 1/8 Corner (1321.45) and doubled to set Northeast Corner. Also measured from East 1/4 Post to Southeast Corner of Section 32 (2643.00).

1994: 3/8" x 18" iron rd from previous witness.

1987; Wilkins & Wheaton Witness 24" Oak South 20° West 20.78'

18" Oak South 50° East 50.15'

1977; G. Smith Witness 12" Oak North 20° West 30.2'

6" Oak North 45° West 45.63'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Southwest Corner Section 28, T. 1 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 3/8" x 18" Iron rered from previous witness (see "B" above) as re-established by Acro Engineering and accepted as a careful and faithful re-establishment of the position of the original corner. Pleased a 20" Harrison monument, with monument box cover.

PK Nail in West Side 12" Oak North 58° East 45.88' CL of "F" Ave North 6.5'

PK Nail in East Side 15" Oak North 14° East 30.22'

PK Nail in South Side 17" Oak South 52° East 50.12'

PK Nail in Southeast Side 24" Oak South 28° West 21.8'

Note all nails were existing in trees.

Signed by *Robert E. Snell* Date 12-05-94

Surveyor's Michigan License No. 9734