

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Alamo Township
1. Public Land Survey

T 1 S R 12 W
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

F-11

2. Property Controlling
in Section
3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

CLERK - REGISTER

94 SEP 21 AM 10 20

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

1 PG 1164

LIBER

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829 - U. S. Government Survey Established-Set 1/4 Section Post.

Yellow Oak 12" South 44° East 46 Lks
White Oak 9" North 36° West 17 Lks

1870 - F. Hodgeman County Surveyor-Found stake hole of 1/4 Section Corner from stumps of 2 witnesses. Planted stone and brick.

White Oak 20" North West 72 Lks
Maple 6" South West 50 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1969 - Wilkins and Wheaton Engineering Company-Found stone and iron. Placed Monument Box over. Brought up with iron.

30" Oak North 16.5'
Maple Southwest 32.6'
16" Maple South 69.0'

1994 - Found two (2) irons over large stone (2½' x 1½' x 1¼') in Monument Box 3' below surface.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 South ¼ Post Section 28, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found large stone (see B. above) and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a 20" Harrison Monument above stone and placed Monument Box over.

Plat Monument (iron in concrete) North 03° East 50.05' CL "F" Ave South 2.2'
PK Nail in East Side 18" Maple North 46° East 28.63'
PK Nail in East Side 14" Maple South 60° East 36.88'
PK Nail in North Side 18" Maple North 50° West 41.65'

Signed by

Robert E. Snell

Date

9-20-94

Surveyor's Michigan License No.

