

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 119

For corners in Alamo Township
Kalamazoo
(County)

Located In:

Corner Code #

- | | | | | | |
|---|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>1S.</u> | R | <u>12W.</u> | <u>G-2</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous
Property in Section | S | T | R | | |
| | S | T | R | | |

REGISTER
 CLERK - REGISTER
Harrison
 97 MAR 20 PM 3 35
 RECEIVED FOR RECORD
 COUNTY OF KALAMAZOO
 STATE OF MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 10, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - Robert Clark, Jr., D.S.,
Set quarter Section post,
Cherry 22" N. 24° E. 15 lks.,
W. Oak 22" S. 58° W. 21 lks.
1872 - E. Strong, C.S., "Stone
18" x 8" x 8" "

1954 - Plat of "Cross Acres" is
recorded L. 20, Pg. 6 and
shows W. 1/4 cor. Section 3 at
1111.27' West of centerline 6th
Street

1974 - R.L. Sauers, R.L.S., L.
1, Surveys, Pg. 533 "Drill
Hole in stone" 40" Box Elder
East 25.94', 30" Cherry West
22.38', 6" Cherry S. 40° E.
27.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with drill hole 0.5' below grade. Stone measures 10" x 10" x 24" and directly under East and West fence. Measured East ±1111' to centerline 6th Street. Stone matches 1974 witness to box elder.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 2-27-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone with drill hole is accepted as a careful and faithful perpetuation of the position of the original corner. Moved stone to West and placed Harrison monument at position of drill hole, Accessories:

- "PK" Nail in West side 8" Twin Cherry N. 25° E. 27.00'
- "PK" Nail in North side 40" Box Elder East 26.21'
- "PK" Nail in Southwest side 10" Maple S. 25° E. 7.30'
- "PK" Nail in South side 10" Elm West 29.40'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 3/18/97