



LC-000013
Page: 1 of 1
07/30/1999 08:24A
Bk-2 Pg-466

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Twp.

SURVEY &
REMONUMENTATION
FEB 08 2000
SECTION

<u>Kalamazoo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 1 S R 12 W	G-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 1-15-99

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: United States Government Surveyors, R. Clark; set post, corner to Sections 27, 28, 33 & 34.
Hickory 9" S. 10° E. 36 lks. White Oak 7" N. 15 1/2° W. 45 lks.
- 1870: F. Hodgman, County Surveyor; "Planted stake with mortar around from 2 witnesses."
- 1907: E. Strong, County Surveyor; drove iron in old br(ick) & mortar.
Apple 5" S. 30° E. ± 104 lks. Hickory 3" S. 70° E. ± 86 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1944: Wilkins & Wheaton Engr. Co.; Placed iron from remains of two witnesses.
16" Oak S. 37° W. 45.4' 12" Wild Cherry S. 47° E. 49.1'
30" Oak S. 78° W. 97.6' 12" Oak S. 79° E. 95.6'
- 1983: Gove Associates; Set monument box over 1/2" iron.
Tel. Pole N. 45° W. 64.63' 24" Oak S. 45° W. 45.85'
18" Oak S. 45° E. 49.69'
- 1999: Found 1/2" iron in monument box. Investigated by digging large hole, found no other physical evidence other than witnesses.
Noted: Nail/Tab in South Side 18" W. Cherry S. 40° E. 49.82'
PK over Nail 12" W. Cherry N. 44° W. 73.30'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11: Southwest corner, Section 27, T. 1 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 15, 1999 and is accepted as a careful and faithful perpetuation of the position of the original corner, found iron in monument box set by Wilkins & Wheaton Engr. Co. in 1944 from two witnesses. Placed 20" Harrison monument in monument box in place of iron.

- 60d Nail/Cap in South Side 20" Oak S. 12° E. 70.40'
- 60d Nail/Cap in South Side 50" Oak S. 42° W. 46.45'
- Nail/Tab in South Side 52" Oak S. 75° W. 98.47'
- PK/Nail in South Side 8" Oak N. 70° W. 99.00'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 7-28-99