

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAMO TWP KALAMAZOO Located In: Corner Code #

Table with 3 columns: Survey Type, T/R, and Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

SURVEY & REMONUMENTATION

NOV 25 1998

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD 98 OCT 12 PM 1 28 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims SECTION
6. IWM Job No. 30755

Grid table with columns A-L and rows 2-13. A small circle is marked in the intersection of column H and row 10.

I, Allen H. McMachen, in a field survey on January 20, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.
1874 - Ed Strong, C.S., "Stone - Intersection"
1994 - Jensen Land Surveying, "Found 1" pipe over stone", 20" Willow N. 50° W. 38.2', 2' East of Traveled centerline, W. end CMP West 18.4', measured East 2625.55' to iron at E 1/4 cor. measured South 2634.28' to iron at South 1/4 cor. (Jensen Land Surveying had knowledge that the roadway had washed out at C 1/4 corner location after his 1994 survey and had removed stone.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in monument box 1' below road surface per 1994 witness to willow. Removed iron and dug to depth of 4' and probed an additional 1' finding no additional evidence of corner. Centerline of 18" culvert is South ± 1.7'. Current culvert is not the one Jensen witnessed to. Measured South 2633.97 feet to iron at S 1/4 corner and measured East 2625.98 feet to a found iron rod (6.95' Southwest of true Section corner and iron held for above 1994 survey) near E 1/4 corner. Measured from iron at C 1/4 corner East 2631.31' to true E 1/4 corner (found drilled stone). Replaced iron in box.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 2/19/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. Found 1/2" iron rod is accepted as the best available evidence of the position of the corner. Replaced found 1/2" iron with a 30" Harrison Monument and brought up box to road surface. Accessories:

- Nail & Tab in N.E. side of Easterly trunk 20" Twin Willow N. 60° W. 37.43'
Nail & Tab in S.E. side 20" Cottonwood S. 30° W. 64.64'
Notch in West end 18" CMP N. 88° W. 20.67'
Notch in East end 18" CMP N. 84° E. 19.49'



Signed by Allen H. McMachen Surveyor's Michigan License No. 16935

Date 10/9/98