

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Township Located In: _____ Corner Code # _____
Kalamazoo (County)

| | | | | | |
|--------------------------------------|---|------------|---|-------------|-------------|
| 1. Public Land Survey | T | <u>1S.</u> | R | <u>12W.</u> | <u>H-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

6. IWM Job No. 30755

I, Allen H. McMachen, in a field survey on January 6, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - Robert Clark Jr., D.S., Set quarter Section post, Sugar 24" N. 60° W. 6 lks., Ironwood 7" S. 70° E. 33 lks..
- 1903 - Ed Strong, C.S., "Found stone correct by measure. All-bearing trees gone. Set crockery & brick around stone. Sugar 10" N. 45° E. 47½ lks., Elm 6" S. 50° W. 23 lks., surveyed the West half of Southeast quarter, Section 27 into 3 equal parcels North and South (13.27 1/3 each) (876.04').
- 1959 - W.D. Ingersoll, R.L.S., Placed iron on line and split being 2630.17 feet from Section corners to East and to West.
- 1985 - Ingersoll, Watson & McMachen, Inc., Found iron rod 16.13 feet Easterly of iron placed in 1959. Easterly iron had been held by other surveyors. Dug below Easterly iron and found second iron (very old) directly under surface iron. Top of second iron was 1.7' below road surface. Replaced iron and held for survey.
- 1990 - Ingersoll, Watson & McMachen, Inc., Found iron rod used in 1985 survey 16.13 feet Easterly of iron placed in 1959. Nail & Tab in U. Pole S. 40° E. 80.1', Twin locust S. 65° E. 87.7', Measure West 2646.29 feet to Southwest corner, Section 27.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" pointed iron 2646.16 feet East of Southwest corner, Section 27 and 2633.97 feet South of Center quarter corner, Section 27.

SURVEY & REMONUMENTATION
 NOV 25 1998
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 3/8" pointed iron is accepted as the best available evidence of the position of the original corner. Replaced found 3/8" iron with a 30" Harrison Monument with monument box over, Accessories:

- 60d nail in SW side 18" Hickory N. 25° W. 81.45'
- 60d nail in NW side 14" Maple N. 45° E. 74.86'
- 60d nail in SW side 18" Walnut S. 45° E. 59.84'
- 60d nail in SE side 8" Aspen S. 62° W. 80.69'

igned by Allen H. McMachen
 urveyor's Michigan License No. 16935

Date 10/9/98

LIBER 2 PAGE 318
 CLERK - REGISTER
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 OCT 12 PM 1 28
 Register of Deeds Stamp & File Number

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 0 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |



RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 3/19/98 R. Z. G.