

**SURVEY & REMONUMENTATION**

SEP 14 1998

LIBER 2 PAGE 298

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION            Alamo Township  
 For corners in Kalamazoo  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>1S.</u>	R	<u>12W.</u>	<u>I-10</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 98 MAR 26 PM 3 37  
 J. H. [Signature]  
 CLERK - REGISTER

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on December 31, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1829 - Robert Clark, Jr., D.S., Set quarter Section post, Bl. Ash 16" S. 61½° W. 239 lks., Elm 11" S. 30° W. 223 lks.

1874 - Ed Strong, C.S., "Remains of U.S. & Stake."

1957 - W.D. Ingersoll, R.L.S., "Found stone with drilled hole, depth-just into muck 2 to 2.5' set ½" iron over hole.", 18" Elm S. 89° W. 20.2', 8" stump S. 84° W. 34.2', 1.5' X 1.5' X 4' S.E. corner conc. fence post, N. 55° W. 66.55', P.P. S. 11° E. 118.15', Pencil rod S. 45° W. 6.95', Centerline 8th Street West ±4'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found pencil rod (1957 witness) and meas. N. 45° E. 7' and dug to depth of ±3.5 feet finding stone with drilled hole.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 2-19-1998  
 R.H.S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found stone with drill hole is accepted as the best available evidence of the position of the original corner. Moved stone Southeast on its side and placed 30" Harrison monument at position of drill hole, with Monument Box over, Accessories:

- "PK" Nail in East side U. Pole N. 60° E. 114.87'
- Nail & Tab in S.W. side of 4" Elm S. 75° E. 75.09'
- Nail & Tab in S.E. side of 6" Elm S. 25° W. 44.83'
- Nail & Tab in S.W. side of 16" Willow N. 60° W. 51.39'



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 2/24/98