

7-2
 SURVEY &
 REMONUMENTATION
 2423
 AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Kalamazoo (County) Located in: Corner Code #

Alamo Township
 1. Public Land Survey T 1 S R 12 W J-7
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 95 JUN 6 AM 9 05
 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 1 1304

I, Robert E. Snell, in a field survey on April 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Survey; Set 1/4 Section Post.

Wh. Oak 6" North 37° East 35 Lks
 Wh. Oak 15" South 14° West 70 Lks

1904: Ed Strong, County Surveyor; North 1/4 Post Section 23--Dug thoroughly but found nothing. Set stone, large one, and 3 brick from 2 Bearing trees of 1878, which point agreed with doubled line from South.

Maple 14" South 25° West 43 Lks
 Butternut 14" North 06° West 49 Lks

Set stake and brick East (Centerline of Road, 50 Lks)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1963: Kalamazoo County Road Commission; Road plans show witnesses to North 1/4 Post. Stone removed during road construction and replaced by witnesses.

3/4" Steel Rod

Maple 22" South 10° East 40.88'
 Maple 36" South 65° West 45.89'
 Telephone Pole North 60° East 76.94'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 9-15-94

1978: Acro Engineering, Robert Sauers, Ingersoll Watson & McMachen; Recorded LCRC 1-710 & 1-76;

1979: Donald Pitts, Surveyor; LCRC 1-794, Same as Kalamazoo County (1963)

1994: Wilkins & Wheaton Engineering Co.; Found 3/4" Iron rod. Dug a hole 6' x 4' and to 7' depth and found nothing else. Noted road had been reconstructed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 North 1/4 Post Section 23, T. 1 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994 and is accepted as a careful and faithful reestablishment of the position of the original corner. Found 3/4" x 24" iron rod. Removed iron rod and set 20" Harrison monument in its place with a monument box over.

Exist. PK Nail in West Side Guy Pole South 22° East 19.48' CL Ravine Rd East 34'
 Exist. Double Head Nail in 36" Maple South 54° West 45.58'
 Exist. PK Nail in South Side Power Pole South 40° East 107.53' CL "D" Ave North 12'
 Center of Monument Box North 64° East 46.01'

Signed by Robert E. Snell Date 6-02-95
 Surveyor's Michigan License No. 9734