



LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAMO TWP
KALAMAZOO
(County)

Located In:	Corner Code #
1. Public Land Survey	T 1S. R 12W. J-11
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 31951

I, Allen H. McMachen, in a field survey on April, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11									●			
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - Robert Clark Jr., D.S., Set quarter Sec. post, Wh. Ash 8" N. 68° W. 32 lks., Wh. Oak 20" S. 13° E. 12 lks..
- 1907 - Ed Strong, C.S., "Found stake hole from B.T., Wh. Oak North, set new stake."
- 1957 - W.D. Ingersoll, R.L.S., "Found stone (about 3' X 4') at depth of 5.5', brought it up with a 1/2" iron." Street sign S. 34° E. 23.6', road sign (↔) S. 17° W. 12.25', P. Pole #8668 S. 10° W. 24.85', P.Pole #8869 N. 30° W. 63.0 feet, centerline "F" Ave. North 3.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod with IWM cap in mon. box per 1957 witnesses. Dug 3' X 3' hole, 5.5' deep and found very large stone directly below found iron. Stone corners and edges were not within limits of excavation. Stone had no visible markings.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8-19-1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron over large stone is accepted as the best available evidence of the position of the original corner. Replaced found iron with a 30" Harrison Monument and monument box over, Accessories:

- SE corner of concrete pad N. 30° W. 147.80'
- 60d nail in South side of 14" Maple N. 35° E.96.30'
- 60d nail in South side of 10" Maple S.70° E. 59.02'
- Nail (existing) in West side of U. Pole S. 25° W. 97.29'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 11/10/99