

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 pg 1169

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 SEP 21 AM 10 21

CLERK - REGISTER
[Signature]

Register of Deeds Stamp & File Number

For corners in

KALAMAZOO

(County)

Alamo Township

1. Public Land Survey

Located In:

Corner Code #

T 1 S R 12 W

K-1

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert E. Snell, in a field survey on April 19, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - U.S. Government Survey-Intersected Baseline 454 Lks East of $\frac{1}{2}$ Section Post. Set Post at Intersection Corner to Sections 1 and 2.
Beech 8" South 43° East 39 Lks Elm 12" South 14° West 48½ Lks

1876 - Ed Strong County Surveyor-Stone and Well Brick.
White Oak 36" South 86° East 117½ Lks

1893 - Ed Strong County Surveyor-Found cobbles and stake hole. Set drilled stone. Stone 6"x5"
Sugar Maple 8" South 43° West 6 Lks

1960 - MSHD-Found stone and Brick, raised with 5/8" Rod
7" Cherry S 40° W 35.68', 14" Cherry S 45° E 47.8', 9" Cherry S 65° E 68.77', Power

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Pole N 45° E 41.65'

1994 - Found 5/8" Rod in Monument Box over drilled stone and brick as called for in Michigan State Highway Department witness notes and LCRC (LI P.157-1979). Below drilled stone found a notched stone over reminence of wood stake in marl soil. Original accessories not recovered.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5/18/94 R.E.F.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Northwest Corner Section 1, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1994. Found 5/8" Rod (MSHD) over drill stone and brick (Ed Strong County Surveyor) over notched stone and stake remains (original corner) and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed drilled stone and placed 20" Harrison Monument over notched stone and stake. Placed Monument Box over.

MSHD Tab	Power Pole	North 35° East 51.92'	CL of Rd to E
PK Nail in East Side	10" Twin Ash	South 32° West 51.32'	North 7.0'
PK Nail in West Side	8" Maple (Twin)	North 102.16'	
"X" Notch in West End	Top of Concrete Drive Culvert	South 78° East 132.85'	

Signed by *Robert E. Snell* Date 9-19-94

Surveyor's Michigan License No. 9734

