

**SURVEY & REMONUMENTATION**

APR 27 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALAMAZOO

(County)

Alamo Township

Located In:

Corner Code #

- |                                       |                            |            |
|---------------------------------------|----------------------------|------------|
| 1. Public Land Survey                 | T <u>1</u> S R <u>12</u> W | <u>K-2</u> |
|                                       | T _____ R _____            | _____      |
|                                       | T _____ R _____            | _____      |
|                                       | T _____ R _____            | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____    | _____      |
|                                       | S _____ T _____ R _____    | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____    | _____      |
|                                       | S _____ T _____ R _____    | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                            |            |
| 5. Private Claims _____               |                            |            |

CLERK - REGISTER

LIBER

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 SEP 21 AM 10 21  
 1 PG 1170

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on April 28, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - Original Corner set by U. S. Government Land Office Survey-Set  $\frac{1}{4}$  Post.  
 Beech 12" South  $06^\circ$  West 25 Lks Beech 8" North  $88^\circ$  East 15 Lks
- 1876 - Ed Strong County Surveyor-Set Stone.  
 Black Walnut 14" North  $14^\circ$  East 116 $\frac{1}{2}$  Lks Corner Apple 10" North  $73^\circ-40'$  W 79 $\frac{1}{2}$  Lks
- 1893 - Ed Strong County Surveyor-Found Good  
 Black Walnut 12" South  $80^\circ$  West 83 Lks Black Walnut 16" North  $30^\circ$  West 87 Lks
- 1926 - Wilkins and Wheaton Engineering Company-Found Drill Stone  
 Black Walnut 24" South  $80^\circ$  West 54.7' Black Walnut 30" North  $30^\circ$  West 57.4'
- 1960 - MSHD-Found Drilled Stone. S  $79^\circ$  W 22.20' 23" Hickory, N  $65^\circ$  E 19.05' 9" Locust,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: S  $62^\circ$  E 26.33' 17" Hickory

- 1994 - Wilkins and Wheaton Engineering Company-found drilled stone (6" x 8" x 4") with evidence of stake hole below in undisturbed dirt. A 5/8" Rod was found 4.92' South and 3.25' East of drilled stone assumed to be corner set by David Peabody in 1975 (LCRC L.1-P.805). No surface accessories recovered.

**RATIFIED**  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 7/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**K-2** West  $\frac{1}{4}$  Post Section 1, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found drilled stone and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 16" of 20" Harrison Marker over stone with a Monument Box over.

PK Nail in North Side	Power Pole	North $52^\circ$ East	80.96'
PK Nail in North Side	34" Walnut	South $76^\circ$ West	22.13' (nail/tab 21.84')
Nail/Tab	18" Walnut	North $20^\circ$ East	76.04'
PK Nail in South Side	8" Elm	South $45^\circ$ East	38.61'
Trav. CL of 10th Street		East	2.15'

Signed by

*[Signature]*

Date

9-21-94

Surveyor's Michigan License No.

