

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2PAGE 319

For corners in Alamo Township
Kalamazoo
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	1S.	R	12W.	K-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 OCT 12 PM 1 28
J. Smith
CLERK - REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 31134

I, Allen H. McMachen, in a field survey on May 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - Robert Clark, D.S., Set quarter Section post, Wh. Oak 13" N. 65° E. 15 lks., Wh. Oak 14" S. 52° E. 14 lks.
- 1966 - R.E. Sayer (Co. Po. Co.), "Pointed stone" 24" Oak North 17.2', 12" Oak South 9.8'.
- 1955 - W.D. Ingersoll, R.L.S., "Found pointed stone (11" X 6" X 5") at fence corner" (no wits taken).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone (11" X 6" X 5") next to sign ("Survey marker - Do not disturb"). Stone had small chiseled "X" at point. Stone was in line with fence remnants to South, North and East. Fence corner was gone but loops of fence were found around stone.

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5/21/98 R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone is accepted as the best available evidence of the position of the corner. Removed stone, bored hole for Harrison Monument and placed stone in bottom of hole and on East side of corner location. Placed 30" Harrison Monument in place of point of stone, Accessories:

- Nail & Tab on East side 44" Oak N. 20° E. 14.40'
- Nail & Tab on S.E. side 26" Oak N. 70° E. 40.50'
- Nail & Tab in West side of 20" Oak S. 05° E. 10.29'
- Nail & Tab in Northerly side 8" Oak S. 60° W. 33.27'



Signed by Allen H. McMachen

Date 9/30/98

Surveyor's Michigan License No. 16935