

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 1 S R 12 W	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY'S
REMONUMENTATION
PEER GROUP
10/17/96

A. Description of original monument and accessories and/or subsequent restoration:

- 1827: United States Government Surveyors; set post, corner to Sections 35 and 36.
Beech 9" N. 25° E. 17 lks.
Beech 5" N. 42° W. 20 lks.
- 1873: Ed Strong, County Surveyor; Southeast corner - Beech 10" S. 10° E. 53 lks. and stone by Hodgman. 3.53 ch. (232.98') East of Oshtemo corner.
- 1880: F. Hodgman, County Surveyor; "corner destroyed. I replaced it by measuring East 3.53 ch. from the corner of Sections 1 & 2 Oshtemo and by course and distance from one bearing tree, set stone."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1900: Ed Strong, County Surveyor; confirms 3.53 chains distance between corners.
- 1959: D. Hooth, M.S.H.D. Surveyor; found chiseled stone.
11" Pear N. 30° W. 32.94' T. Pole N. 07° W. 34.67'
12" Elm N. 56° W. 45.95'
- 1974: Wilkins & Wheaton Engr. Co.; found stone in bound - Southeast corner Section 35, Alamo.
12" Apple N. 10° W. 32.94' 6" Elm S. 10° W. 35.70'
Northeast corner Section 2 Oshtemo - bound in intersection of 10th St. and "G" Ave. West 232.70'.
- 1996: Found stone with drill mark 13" below surface in monument box with brick around - stone is 14"x8"x?

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13: Southeast corner Section 35, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on October 17, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone with drill mark as set by F. Hodgman, County Surveyor in a 1880 survey. Placed 12" of 20" Harrison Monument set in concrete over stone in monument box 232.71' East of iron in monument box for the corner of Section 1 and 2, T. 2 S., R. 12 W.
PK Nail in South Side 6" W. Cherry N. 58° E. 35.48'
PK Nail in Southwest Side 14" W. Cherry S. 46° E. 57.79'
PK Nail in Southeast Side 12" Twin W. Cherry S. 50° W. 63.24'
PK Nail in Southwest Side 8" W. Cherry N. 32° W. 35.48'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-15-96

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 NOV 15 PM 1 59
James J. [Signature]
CLERK-REGISTER

LIBER 2 PAGE 086

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													