

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 089

For corners in Alamo Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 1S R 12W	L-06
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 NOV 15 PM 1 58
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors.

1882: E. Strong, County Surveyor; was shown an old corner for center. Probably by Allegan ... Surveyor. Set stake.

1891: E. Strong, County Surveyor; found stake of former survey.

- Y. Oak 22" Northeast 40 lks.
- Y. Oak 6" Northeast 16 lks. stone

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10/17/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1928: Wilkins & Wheaton Engr. Co.; from field notes - center 1/4 by witness stumps.

1991: Don Gilchrist, R.L.S. #13583; L.C.R.C. L-1, P-879, found stone/drill hole and ring of stones.

- 22" Oak N. 25° E. 10.68'
- 12" Hickory S. 45° E. 21.38'
- 24" Oak S. 01° W. 31.65'
- 5" Hickory S. 45° W. 21.65'

1996: Found 4 large stones (6"-8" dia.) largest stone has drill hole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-06: Center 1/4 post, Section 13, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on October 17, 1996 and is accepted as the best available evidence of the position of the corner. This position not established by original government surveyors. Found 4 large stones (6"-8" dia.) largest stone having a drill hole. Stone set by Ed Strong, County Surveyor in a 1891 survey. Placed a 30" Harrison Monument and laid stone with drill hole on Northwest side of monument down about 8".

- Exist. Nail in Southeast Side 18" Oak N. 45° E. 10.70'
- PK Nail in North Side 12" Hickory S. 70° E. 21.55'
- Exist. Nail in East Side 22" Oak Stump S. 08° W. 31.68'
- Exist. Nail in North Side 7" Hickory S. 68° W. 21.61'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-14-96