

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'98 OCT 20 AM 11 25

Timothy Johnson

CLERK - REGISTER

LIBER 2PAGE 343

Register of Deeds Stamp & File Number

KALAMAZOO

(County)

Located In:

Corner Code #

1. Public Land Survey

T 1S R 12W

M-7

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat

5. Private Claims

I, WILLIAM K. CRANE, P.S., in a field survey on OCTOBER, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., DEC. 1829, G.W. HARRISON, D.S.:

8" W.O., N9°W, 30 LINKS

36" W.O., S.26°W, 19 LINKS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ALAMO TWP.

SURVEY &
REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON NO. 26463 INSIDE A 2" PIPE IN A MONUMENT BOX. REMOVED IRON, PIPE, AND BOX. DUG 3' AND FOUND WOOD STAKE AND STONE. SET HARRISON MONUMENT AND MONUMENT BOX.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-19-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND STONE AND STAKE IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER. RAISED STONE AND STAKE WITH HARRISON MARKER AND MONUMENT BOX.

S.W. COR. OF SEC. 18, T1S, R11W; NORTH, 26.85'
FND "PK" NAIL & SPOTTER IN E. SIDE OF U.P; S.44°E, 61.32'
FND NAIL IN E. SIDE OF 16" WALNUT; N.31°W, 51.87'
FND NAIL IN S.E. SIDE OF U.P; N.49°E, 45.48'
IN CENTERLINE OF ROADS NORTH, SOUTH, EAST, & WEST

Signed by *William K. Crane*

William K. Crane, P.S.

Date 10/19/98

Surveyor's Michigan License No.: 29243

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

REVISED OCT., 1995

