

'95 AUG 24 PM 3 58

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAMO TOWNSHIP
KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>1</u> S <u>R12</u> W	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. Jones
CLERK-REGISTER

LIBER 1 1317

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen field survey on April 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - William Brookfield, D.S. Set Post
Wh. Oak 12" S. 27° W. 7 lks.
Wh. Oak 14" N. 53° W. 35 lks.
- 1963 - Mich. State Hwy. Dept.
1/2" Iron in 2" pipe
15" Hickory S. 60° W. 58.89'
14" Hickory N. 50° E. 83.15'
51" Oak S. 70° E. 34.87'
- 1920 - Kal. Co. Rd. Comm. Found Stone
Cor. fence post N. 50° W. 35.8'
Oak 30" S. 87° E. 31.0'
Sassafras 3" S. 17° W. 50.7'

Also found stone North 20' (S.W. Cor., Sec. 19, Cooper Twp.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" X 12" Iron rod in 2" pipe in mon. box., removed Iron and found a second 1/2" Iron (0.1' S. & 0.05' W.), removed second Iron and found large rounded stone 3' below surface. No "X" or drill hole was visible, middle of stone fit location of first 1/2" Iron found. Also found stone at S.W. corner, Sec. 19, Cooper Twp. 19.40' North (Gov't 19.8').

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-20-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over found Stone and Monument box over. Accessories:

- Nail & Tab in S.E. Side 6" Maple N. 30° E. 67.13'
- Chiseled "X" in North End Conc. Culvert N. 50° E. 63.22'
- Nail & Tab in S.W. Side 8" Oak S. 50° E. 44.09'
- Nail & Tab in N. Side 26" Hick. S. 64° W. 58.43'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 5/24/95