

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Charleston Township

1. Public Land Survey

T 2 S R 9 W

C-1

T

R

T

R

T

R

2. Property Controlling in Section

S

T

R

S

T

R

3. Miscellaneous Property in Sec.

S

T

R

S

T

R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

CLERK - REGISTER

LIBER

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 94 SEP 21 AM 10 21

1 PG 1172

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on February 11, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U.S. Government Survey-Intersected North Boundary 195 Lks West of Post. Set Post at intersection of corner to Section 5 and 6.

White Oak 18" South 37° East 40 Lks
 White Oak 18" South 24° West 62 Lks

1883 - F. Hodgeman County Surveyor-Ran North 37° West, 40 Lks from U.S. Bearing Tree and found stake hole. Bored 3', put 1' earthen post in bottom then 1' of stone and 1' earthen post on top.

Hickory 6" South 10° West 4 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - Found 3" clay tile at surface from existing witness tree.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 5/18/94 R.E.F.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-1 Corner to Sections 5 and 6, T. 2 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1994. Found 3" round clay tile as called for in 1883 Remonumentation Survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed remonumentation sleeve over tile.

PK Nail in East Side 18" Hickory South 08° West 2.40' (1883 Witness)
 PK Nail in North Side 24" Oak South 84° West 24.45'
 PK Nail in North Side 12" Hickory South 86° East 32.15' in E. Fence Line
 PK Nail in West Side 15" Hickory South 40° East 17.81'
 South line of fence West 1.3'

Red by

Robert E. Snell

Date

9-19-94

Surveyor's Michigan License No.

9734