

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo  
(County)  
**Charleston Section 6**

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>2</u> S R <u>9</u> W | <u>C-2</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 MAR 15 PM 1 38  
 CLERK - REGISTER  
*Janet [Signature]*  
**LIBER 1 PG 1118**  
 Register of Deeds Stamp & File Number

I, Robert E. Snell in a field survey on January 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established by U. S. Government Survey in 1836. Set Post.  
 Wh. Oak 24" South 11°-E 60 Lks (39.6')  
 Wh. Oak 9" North 59°-W 20 Lks (13.2')
- 1883-F.Hodgeman County Surveyor-ran North 11°-W, 60 lks from stump of U.S. bearing tree and found stake hole. Bored 3' and put in earthen post.  
 Y. Oak 12" North 88°-W 15 Lks (9.9')  
 Hickory 8" North 65°-E 7½ Lks (4.95')

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found solid clay tile with "X" on top and stone around. One witness still standing.

*R. E. Snell*  
**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
 1-20-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 C-2 East 1/4 Post Section 6, T. 2 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on January 20, 1994. Found solid clay tile with "X" on top with stones around and a 24" Hickory North 75°-E (N-65 E) 5.51 (4.95) as assumed to be a witness tree as surveyed in 1883 and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed remonumentation sleeve over tile.
- PK Nail in S side 12" Hickory South 87°-E 42.11'  
 PK Nail in W side 28" Hickory South 80.74'  
 PK Nail in S side 24" Hickory North 75°-E 5.51'  
 PK Nail in Wly side 8" B.Ash North 20°-W 6.42'  
 Fence corner with fence to North and East-Old fence to West, North 1.5'

Signed by *Robert E. Snell* Date 3-15-94  
 Surveyor's Michigan License No. 9734