

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

For corners in

KALAMAZOO

(County)

Charleston Township

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In:

Corner Code ##

1. Public Land Survey	T	<u>2</u>	S	R	<u>9</u>	W	<u>C-4</u>
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

CLERK - REGISTER

James J. [Signature]

94 SEP 21 AM 10 21

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LIBER 1 PG 1168

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U.S. Government Survey-Set 1/4 Section Post

Burr Oak 8" North 27° West 20 Lks
Burr Oak 7" South 15° East 30 Lks

1877 - F. Hodgeman County Surveyor-Found stake hole from one witness stump. Set stake and stone

White Oak 12" North 86° East 20 Lks
White Oak 16" South 15° East 86 Lks

1883 - F. Hodgeman County Surveyor-Replaced stake with 2 1/2' of earthen post with stone under and

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: around the top of it.

1994 - Found 3" round tile with "X" in top at surface of the ground with stones around the top of it. One 1877 witness still live and standing.

RATIFIED *R.E.S.*
**BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
7/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Quarter Section Corner between Sections 7 and 8, T. 2 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Peer Group on May 17, 1994. Found 3" round tile as called for in 1883 Remonumentation Survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed remonumentation sleeve over tile.

PK Nail in East Side	Power Pole	North 03° East	61.80'
PK Nail in North Side	50" Oak	East	14.48' (1877 Witness)
CL of	10" Pine	North 85° West	66.42'
CL of	10" Pine	North 25° East	58.70'

Signed by

Robert E. Snell
9734

Date

9-21-94

Surveyor's Michigan License No.

9734