

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo

(County)

Located In:

Corner Code ##

Charleston Section 20

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>2</u> S R <u>9</u> W | <u>C-8</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on January 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by U.S. Government Survey in 1826-Set Post.

- Wh. Oak 12" N 89°-W 4 Lks ( 2.64')
- Wh. Oak 10" N 60°-E 22 Lks (14.52')

1883-F.Hodgeman County Surveyor-found stake and stone of former survey. Bored down 3' and put in one foot of stone with two-one foot earthen post over. Even with surface.

Black Walnut 3" East 35 ½ Lks (23.43')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found solid clay tile at surface 1.0' south of base of east and west fence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 West 1/4 post Section 20, T. 2 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on January 20, 1994. Found solid clay tile with "X" on top as called for in 1883 remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed monumentation sleeve over tile.

- PK Nail in W side 18" Walnut N 05° E 32.43'
- PK Nail in SE side 18" Oak N 50° E 47.80'
- PK Nail in N side 14" Oak N 85° W 6.18'
- PK Nail in NE side 14" Oak S 50° E 21.57'
- A large (1.5' x 1.8') rock sits N 15° W 6.0'±
- PK Nail in S side 12" Oak N 12° W 2.57'

Signed by Robert E. Snell Date 3-15-94

Surveyor's Michigan License No. 9734

CLERK - REGISTER

LIBER

1 PG 1113

Register of Deeds Stamp & File Number

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 1994 MAR 15 PM 1 37

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**RATIFIED**  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 1-20-94