

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo

(County)

Charleston Section 30

Located In:

Corner Code ##

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>2</u> S R <u>9</u> W | <u>C-9</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                           |            |
| 5. Private Claims _____               |                           |            |

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 MAR 15 PM 1 38  
 CLERK-REGISTER  
 LIBER 1 PG 1117

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on January 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by U. S. Government Survey in 1826. Set Post.

Wh. Oak 6" North 70°-E 21 Lks (13.86') Wh. Oak 10" South 82°-W 37 Lks (24.42')

1883-F. Hodgeman County Surveyor-could find nothing very satisfactory, measured to nearest Quarter Post-North, East, and West, and near the point. Found a Wh. Oak tree standing in the line of the fence which appears as if it must have been the U.S. bearing tree though the marks are not plain. There are no other indications of any other tree which could have been a witness tree anywhere near. Rane North 82°-E, 37 Lks from this tree and set two foot earthen post with one foot of stones beneath it. A station tree of U.S. Survey with marks plain upon it now stands South of this Post. 10.24 Ch. (675.84).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Found solid clay tile with "Mushroom" top at surface with stones around.


**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 1-20-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Corner Post for Sections 19, 20, 29 and 30, T. 2 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on January 20, 1994. Found solid clay tile with stones around as set in 1883 remonumentation by F.Hodgeman in 1883 and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed tile and broke off top and reset solid clay tile with monumentation sleeve over.

- |                                   |                |                                |
|-----------------------------------|----------------|--------------------------------|
| PK Nail in Nly side of 4" Elm     | N 40°-W 12.69' | PK Nail in E side 15" W.Cherry |
| PK Nail in Wly side of 12" Elm    | N 12°-W 35.18' | S 05°-E 23.40'                 |
| PK Nail in Wly side of 14" Elm    | N 25°-E 41.85' |                                |
| PK Nail in Nly side of 8" Db1.Elm | N 58°-E 20.50' |                                |

Signed by Robert E. Snell Date 3-15-94  
 Surveyor's Michigan License No. 9734