

**SURVEY &
REMONUMENTATION**

FEB 18 1994

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSIONER OF LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 29 AM 10 31

For corners in

<u>Kalamazoo</u> <small>(County)</small> <u>Charleston Twp.</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>25</u> R <u>9</u> W	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James E. Boynton
CLERK-REGISTER

LIBER **1** PG **1045**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James E. Boynton, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter post established by U.S. Government Deputy Surveyor John Mullet in 1826. Remonumentation by F. Hodgeman in 1883, set standard tile; accessories: W.O. 12, S. 37° E. 3 5/4, not found. Tile found in 1974 by Don Gilchrist and re-witnessed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile from 1974 witnesses:
8.5' North of bottom of ridge
P.P. S. 30° W. 43.96'
24" Oak S. 85° E. 48.68'
4" Popal S. 05° E. 3.30'
Power line west 29'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile and accepted as carefull and faithfull perpetuation of the original corner location. Set standard remonumentation sleeve over tile, new witnesses:
Corner is 29' East of powerline and 8.5' N. of bottom of ridge.
30" Maple S. 85° E. 48.72' ; 10" popal S. 05° E. 3.22'
Power pole S. 30° W. 43.92' ; 8" Elm South. 9.82'

Signed by James E. Boynton Date 12-8-93
Surveyor's Michigan License No. 29239