

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Charleston Township

T 2 S R 9 W

D-9

1. Public Land Survey

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 94 DEC 30 AM 9 18
 CLERK - REGISTER

LIBER 1 PG 1242

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 24, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | ☉ | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1826: U.S. Government Survey; Set 1/4 Section Post.

Wh. Oak 9" North 57° East 11 Lks
Wh. Oak 10" South 70° West 43 Lks

1872: S. Hodgman, County Surveyor; Found stake hole, correct by trace of witnesses. Set iron sleigh shoe and stones. Set side stones North and South (50 Lks).

1883: F. Hodgman, County Surveyor; Found stake, stones and iron for corner and side stones of former survey standing. The road has been filled up over the corner and I left the corner stone in place and put 2' of earthen post over with stones around.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 6" Piece of tile over stone in monument box and found iron sleigh shoe with stones around 20" below surface. Also, found side stone 50 Lks (33') North.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 7-21-94
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 South 1/4 Post Section 20, T. 2 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found sleigh shoe as set in 1872 survey by S. Hodgman and mentioned in 1883 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 20" Harrison monument with monument box over sleigh shoe.

| | | | | | |
|---------------------------|-----------------|-------|----------|--------|--------------------|
| Center Line "L" Avenue | | South | 4.0' | | In Line with fence |
| PK Nail in East Side | 38" Oak | North | 20° West | 31.58' | to North |
| PK Nail in Northeast Side | 12" Hickory | South | 32° East | 36.53' | |
| PK Nail in East Side | 15" Red Oak | South | 10° West | 25.31' | |
| PK Nail in | 12" Quad Cherry | South | 52° West | 39.73' | |

Signed by Robert E. Snell

Date 12/28/94

Surveyor's Michigan License No. 9734