

# SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'94 DEC 6 PM 3 55

For corners in

Kalamazoo

(County)

Charleston Township

Located In:

Corner Code #

1. Public Land Survey		T <u>2</u> S R <u>9</u> W		D-11	
		T _____ R _____		_____	
		T _____ R _____		_____	
		T _____ R _____		_____	
2. Property Controlling in Section	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	
3. Miscellaneous Property in Sec.	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

*James J. [Signature]*  
CLERK - REGISTER  
LIBER 1 PG 1184

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			●										
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1826 - U.S. Government Survey-Set 1/4 Post

Hickory	7"	South	30°	East	18 Lks
Ironwood	8"	North	37°	West	13 Lks

1883 - F. Hodgeman, County Surveyor-Found old stake at intersection of fences. No witnesses. Bored 3', put 1' of brick in the bottom and 2' earthen post over.

Elm	26"	North	09½°	East	91 Lks
Hickory	4"	North	45°	West	65½ Lks

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994 - Found "mushroom top" 3" round tile at surface from witness on file.

Intersection of fences East, North and South

Fence West	South				35.5±'
12" Hickory (Oak)	North	85°	East		7.23'
4" Oak	North	20°	West		9.18'
12" Catalpa	South	40°	West		23.31'

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
4/21/94 L. E. [Signature]**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-11 South 1/4 Post Section 29, T. 2 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" round tile with "mushroom top" at surface as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Removed "mushroom top" and placed remonumentation sleeve over tile.

Exist Nail/Tab in Southwest Side	4" Oak	North 10° West	9.20'
PK Nail in North Side	16" Oak	North 84° East	8.97'
PK Nail in North Side	24" Catalpa	South 80° East	36.21'
PK Nail in North Side	16" Maple	South 60° West	20.14'

Signed by *Robert E. Snell* Date 11-30-94  
Surveyor's Michigan License No. 9734