

FEB 06 1999

LIBER 2 PAGE 437

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Charleston Twp.

Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey

T	2S	R	9W	E-09
T		R		
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
98 DEC 29 AM 11 26  
J. J. [Signature]  
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Oct. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

*R.E.S.*  
**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP, 11-19-1998**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set post, corner to Sections 20, 21, 28 & 29.

Hickory 4" S. 67° W. 27 lks.  
Hickory 4" S. 21½° E. 29 lks.

1872: S. Hodgman, Deputy County Surveyor; "set iron stake, stone & brick at the measurements marked on plat (opposite) and marked Black Oak 18" S. 13½° E. 161½ lks. This places the corner very near the center of the road as the fences now stand and all parties seemed to (be) perfectly satisfied."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1883: F. Hodgman, County Surveyor; "found stone, iron & brick and witness trees of former survey standing. Bored 3 ft., filled bottom with stone and broken brick and put 1 ft. earthen post over with stones around 4" below the surface of the ground."

1978: Wilkins & Wheaton Engr. Co.; Northeast corner (Section 29) placed by prorating to S. Hodgman: AT&T Pole #2220 N. 45° W. 40', 14" Black Walnut N. 30° E. 80', AT&T Pole N. 80° E. 77.4', 30" Oak S. 80° E. 91.8'

1990: R. Lester, RLS#18998; ½" bar in monument box, Nail/Tag E. side 14" Oak 240° az. 54.2', Nail/Tag N. side 36" Oak 106° az. 91.1', Nail/Tag E. side Utility Pole 322° az. 39.5', Nail/Tab in E. side 12" Oak 205° az. 81.9'

1998: Found old iron, brick & stones 5' to 6' deep near intersection of roads 4.0' East of iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner placed in 1978.

E-09: Southeast corner, Section 20, T. 2 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 19, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found iron, brick and stone 5' to 6' below surface, as placed in 1872 by S. Hodgman and verified in 1883 in a remonumentation survey by F. Hodgman, County Surveyor. Original corner removed during sewer construction. Placed 30" Harrison monument in monument box 4.0' East and 1' South of corner set in 1978 survey.

PK Nail in North Side	12" Oak	S. 40° W.	55.40'
PK Nail in South Side	16" Oak	S. 50° W.	57.3'
PK Nail in East Side	Fence Corner	N. 45° W.	50.29'
Nail/Tab in North Side	36" Oak	S. 80° E.	87.10'

Signed by Robert E. Snell

Date 12-29-98

Surveyor's Michigan License No. 9734