

**SURVEY & REMONUMENTATION**

FEB 26 1998

LIBER 2 PAGE 232

**SECTION LAND CORNER RECORDATION CERTIFICATE**

Charleston Township Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo  
(County)

Located In:

Corner Code #

- |                                    |   |            |   |            |             |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey              | T | <u>2S.</u> | R | <u>9W.</u> | <u>F-13</u> |
|                                    | T |            | R |            |             |
|                                    | T |            | R |            |             |
|                                    | T |            | R |            |             |
| 2. Property Controlling in Section | S |            | T |            |             |
|                                    | S |            | T |            |             |
| 3. Miscellaneous                   | S |            | T |            |             |
| Property in Section                | S |            | T |            |             |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

CLERK - REGISTER

*Janice Brown*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 NOV 19 PM 3 48

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1825 - John Mullett, D.S., Set quarter Section post, Wh. Oak 16" N. 64 1/2° E. 23 lks., Wh. Oak 9" N. 52 1/2° W. 94 lks.

1872 - S. Hodgman, C.S., "Found 1/4 post on South side Sec. 33, Charleston from 1 witness & stump of other, the distance to the witness N.E. is 33 lks. instead of 23 as given in government notes. Witness marks and stake hole plain & unmistakable"

1883 - F. Hodgman, C.S., "Found old stake & one U.S. bearing tree N. 64 1/2° E. 33 lks. alive and stump of other standing N. 54° W. 94 lks. bored 3' put small stone in bottom and old stake & 2 foot earthen post over. 2" above surface in open field."

1995 - W. Crane, P.S., (L.C.R.C., L. 1, Pg. 1425) "Found clay tile 0.5' ± below ground 12" Cherry S. 33° E. 287.64', 14" Tw. Cherry S. 39° E. 231.07', 12" Cherry S. 43° E. 200.83', N. 1/4 cor., Sec. 4, Climax Twp., East 105.09'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found clay tile in tree roots per 1995 witnesses. Found tile is in East-West fence line and 105.1 feet Westerly of N. 1/4 cor., Section 4, Climax Township.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Removed tree roots above tile and placed standard sleeve over tile, Accessories:

Nail in Southerly side of Railroad tie fence post West 1.8'  
Nail in Westerly side of 8" Elm N. 20° W. 58.32'  
Nail in Northwesterly side of 18" Willow S. 55° W. 68.6'  
Placed iron rod East 45.3'

**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
2-27-1997

*R. G. 8*



Signed by *Allen H. McMachen*  
Surveyor's Michigan License No. 16935

Date 11/12/97