

1
2
FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 398

For corners in Charleston Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T 2S R 9W	G-08
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 15
LIBER - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Aug. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post
Wh. Oak 18" S. 14° W. 42 lks.
Wh. Oak 15" N. 74° E. 52 lks.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9/17/98

1883: F. Hodgman, County Surveyor; "Found stake, witnesses of resurvey and stump of one U.S. Bearing Tree standing. Put in 2 ft. earthen post with 1 ft. stone under it and stone about the top.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1940: Andrew Lenderink, Civil Engineer; 1/4 post 42.90' North of centerline U.S. 12.
- 1960: Acro Engineering Co.; three stones, centerline existing U.S. 12 South 42.90'. Fence Post N. 11° W. 78.86' 10" Oak N. 28° E. 79.90' 15" Oak N. 74° E. 52.0'
- 1978-79: Michigan State Highway Dept.; boat spike, traveled centerline Michigan Ave. South 42.4' Steel Fence Post N. 10° E. 18.26' Steel Fence Post N. 40° W. 21.45'
- 1998: Found 1/2"x12" rerod 6" below surface and 1' boat spike below. Dug to 3 1/2' and found no other evidence. Noted South r-o-w fence I-94 North 17.9' Traveled centerline E. Michigan Ave. South 41.91'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-08: East 1/4 post, Section 21, T. 2 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 17, 1998 and is accepted as the best available evidence of the position of the original corner. Found 12" boat spike below 1/2"x12" rerod. Original corner believed to have been removed during construction of I-94 and replaced by MSHD Surveyors. Placed 30" Harrison monument in place of boat spike.

"T" Iron Fence Post	N. 50° E.	31.40'
PK Nail on Top East End Guard Rail Post	S. 55° E.	57.81'
PK Nail on Top Guard Rail Post	S. 30° W.	18.31'
"T" Iron Fence Post	N. 20° W.	21.59'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-18-98