

'94 APR 28 AM 9 11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Sec. 33, Charleston Twp.

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>2</u> S R <u>9</u> W | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

James J. J...

CLERK-REGISTER

LIBER **1** PG **1132**

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 10, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1825-Original corner placed by U.S. Government Survey. Set Post, corner to Sections 33 & 34.
 Y. Oak 9" North 70° East 45 Lks
 Wh. Oak 15" North 48° West 62 Lks
 - 1872-S. Hodgeman, County Surveyor-found both stake holes, verified by Traces (good) of all Witness and measurement from the section corner 1 mile west and the intermediate 1/2 post. Set stone with "X" about one foot below the surface-small stake above.
 - 1883-F. Hodgeman, County Surveyor-Found stone of resurvey by S. Hodgeman, planted earthen post 3' deep with stone beside. Burr Oak 16" South 77° West 14 Lks
 Burr Oak 18" South 55° East 85 Lks
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 3" round tile with "X" on top near fence post.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-17-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-13 Southeast Corner Section 33, T. 2 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 17, 1994. Found 3" clay tile down about 6" as called for in 1883 Remonumentation Survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Place remonumentation sleeve over tile.

PK Nail in North Side	14" Db1. W. Cherry	S 50°-E	65.03'	T CL Road	East 32.7'
Centerline	2" Chain Link			CL PVC Fibre	
	Fence	East	66.36'	Optic Marker	East 10.15'
PK Nail in South Side	14" Oak	N 70°-E	55.32'		
NE C	Cor RR Tie Fence				
	Post	S 20°-W	0.82'		

Signed by *Robert E. Snell* Date 4-26-94
 Surveyor's Michigan License No. 9734