

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'96 MAR 13 PM 3 42

For corners in

Kalamazoo

(County)

Located In:

Charleston Twp.

Corner Code #

- | | | | | | |
|--------------------------------------|---|-------------|---|-------------|-------------|
| 1. Public Land Survey | T | <u>2</u> S. | R | <u>9</u> W. | <u>H-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

James J. Young
CLERK-REGISTER

LIBER **1 1453**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on January 22, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; set 1/4 Section post.
Blk. Oak 16" N. 75^{1/2}° E. 82 lks.
Wh. Oak 6" N. 64^{1/2}° W. 23 lks.
- 1883: F. Hodgman, County Surveyor; found stake with stone around and stump of one U.S. bearing tree Northwest bored 3 ft., put 1 ft. brick in the bottom and 2 ft. earthen post over with stone around.
Hickory 2" S. 85° W. 24 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1937: Wilkins & Wheaton Engineering Co.; found tile 57' West of iron for North 1/4 post Section 3, Climax Township (T. 3 S., R. 9 W.)
- 1996: Found 3" round tile with mushroom head at surface 16.3' East of center line of 36" stump and 57' West of iron pipe.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-15-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13: South 1/4 post Section 34, T. 2 S., R. 9 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on February 15, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "mushroom" head at surface. Removed head and placed remonumentation sleeve over tile.

PK Nail in South side	6" Hickory	S. 78° E.	6.66'
PK Nail in West side	3" Cherry	S. 48° E.	6.52'
PK Nail in West side	4" Cherry	S. 16° E.	3.34'
PK Nail in North side	3" Cherry	S. 50° W.	11.30'
Hodgman Witness (See A)	36" Stump	West	16.3' (15.84')

Signed by Robert E. Snell

Date 3-12-96

Surveyor's Michigan License No. 9734