

**SURVEY &  
REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 6 PM 3 56

COMMISSION

*James J. Jones*  
CLERK-REGISTER

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Charleston Township

1. Public Land Survey

T 2 S R 9 W

I-1

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER 1 PG 1186  
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on September 22, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U.S. Government Survey-Intersected North boundary at Post.

Wh. Oak 12" North 74½° East 80 Lks  
Y. Oak 16" North 81° West 277 Lks

1883 - F. Hodgeman, County Surveyor-Found old stake hole in center of road and in line with fence South. No witnesses. Bored 3', put 1' earthen post in bottom, 1' stone and 1' earthen post over with stones around. Set side stones 40 Lks each North and South.

Pine 4" South 08° East 52½ Lks  
Y. Oak 6" North 23° East 39 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972 - Wilkins & Wheaton Engineering Company-Found 3" diameter solid tile with cross, 1' below surface. Palced 2" iron pipe over.

Large White Stone (above surface) North 20° East 33.2'  
24" Pine South 08° East 34.6' Note: Pine above 52½ Lks= 34.65'

1994 - Found 2" iron pipe over tile (1' below surface). Note: Pine witness of 1883 and 1972. Pine is still standing but now dead.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
11/17/94 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Northwest Corner Section 2, T. 2 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group November 17, 1994. Found 3" round tile as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed 16" of 20" Harrison monument over tile.

PK Nail in West Side 14" Elm South 06° West 29.03'  
PK Nail in Northeast Side 16" Locust North 51° West 34.97'  
PK Nail in East Side 22" Maple South 30° West 55.82'  
Drill Hole in CL Large White Rock North 20° East 32.98'

Signed by

*Robert E. Snell*

Date

12-5-94

Surveyor's Michigan License No.

9734