

**SURVEY & REMONUMENTATION**

1  
2

MAY 28 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Kalamazoo Located In: Corner Code #  
(County)  
Charleston  
1. Public Land Survey T2S R9W I-13  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

*James R. Young*  
CLERK - REGISTER

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
'96 AUG 26 PM 4 00  
LIBER 2 PAGE 044

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on April 18 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: United States Government surveyors; set post common to Sections 34 and 35.  
Hickory 6" N 7½° W 74 lks.  
Wh. Oak 18" N 83° E 213 lks.
  - 1883: F. Hodgman, County Surveyor; found stone of resurvey by S. Hodgman. Planted earthen post 3 ft. deep with stone beside.  
Burr Oak 16" S 77° W 14 lks.  
Burr Oak 18" S 55° E 85 lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996: Measured West from Harrison monument at Northeast corner of Section 3, T 3 S, R 9 W 25.58'. Found ½"x18" long iron bar over tile 24" below surface. (government jog)

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
7-18-1996

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-13: Southeast corner Section 34, T 2 S, R 9 W; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman, County Surveyor in 1883 remonumentation survey. Placed 20" Harrison monument over tile in monument box.  
Harrison monument on Northeast corner Section 3, T 3 S, R 9 W East 25.64'  
PK nail on West side 22" Maple N 38° E 87.21'  
PK nail on South side 10" Maple East 49.30'  
PK nail on West side 7" Hickory S 36° E 66.40'  
Nail/tab on South side Railroad tie fence post N 84° W 19.19'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 8-22-96