

**SURVEY &
REMONUMENTATION**

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 6 PM 3 56

For corners in

COMMISSION

Kalamazoo

(County)

Located In:

Corner Code #

Charleston Township

1. Public Land Survey

T 2 S R 9 W

J-11

T R

T R

T R

S T R

2. Property Controlling
in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

James J. Gump

CLERK-REGISTER

LIBER

1 PG 1187

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert E. Snell, in a field survey on September 23, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U.S. Government Survey-Set Post for 1/4 Section Corner.

Y. Oak 18" North 57° West 12 Lks
Wh. Oak 14" North 11° East 16 Lks

1883 - F. Hodgeman, County Surveyor-Found stone said by Slyter to have been known by him for corner for 25 years and undisputed. Bored 3', put in 1' of broken brick and 2' earthen post over with stones around and marked.

Y. Oak 12" South 03° East 51 Lks
Apple 4" North 02° West 50 1/2 Lks
Blk Oak 12" South 70 1/2° East 170 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - Found concrete block and brick over monument box (4" below surface). Found 3" clay tile.

LCRC L-1, P. 455-L. Watson 1971
Southwest Corner House Northeast 65.85'
10" Oak North 45° West 48.25'
7" Oak South 60° West 67.84'

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
11/17/94
R. E. Snell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 South 1/4 Post Section 26, T. 2 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on November 17, 1994. Found 3" clay tile in monument box 4" below surface as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

Exist. Nail/Tab in North Side 18" Hickory North 50° West 47.83' in CL of E-W Road
Southwest Corner House Foundation North 28° East 65.89'
Exist. Nail/Tab in East Side 10" Oak North 20° East 26.77'
Exist. Nail/Tab in North Side 20" Hickory South 56° West 67.75'

Signed by

Robert E. Snell

Date

12-5-94

Surveyor's Michigan License No.

9734