

FEB 08 1999

SECTION

LIBER 2 PAGE 433

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Charleston Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>9W</u>	<u>J-12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 29 AM 11 26
CLERK - REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M		
2	6			5			4			3		2	1		
3															
4	7						8			9		10	11	12	
5															
6	18						17			16		15		14	13
7															
8	19						20			21		22		23	24
9															
10	30						29			28		27		26	25
11															
12	31						32			33		34	35		36
13															

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors.

1972: John Kester, RLS#16046; L.C.R.C. L-1, P-211, Set 1/2" iron in monument box at intersection of North and South and East and West 1/4 lines.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1977: Ingersol, Watson & McMachen; used iron in monument box as center 1/4 post.

1998: Ran North/South and East/West 1/4 line and found iron in monument box to be 0.10' North and 0.18' West of true intersection.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-17-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12: Center 1/4 post, Section 35, T. 2 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 17, 1998 and is accepted as a careful and faithful perpetuation of the position of the corner. Found 1/2" iron in monument box as placed on intersection of 1/4 lines by John Kester, RLS #16046 in a 1972 survey. Placed 30" Harrison monument in monument box in place of iron.

1/2" Iron with Cap (#17617)		North	32.75'
Nail/Tab in East Side	10" W. Cherry	N. 60° E.	45.67'
PK Nail in West Side	10" W. Cherry	N. 38° E.	37.25'
Top at Center	Telephone Pedestal	N. 20° E.	31.51'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-29-98