

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

AUG 27 PM 3 15

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Charleston	T2S R9W	K-11
1. Public Land Survey	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

James J. Young
CLERK-REGISTER

LIBER 2PAGE 056

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 7-18-1996

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
1826: United States Government surveyors; set section corner common to Sections 25, 26, 35 and 36.
Beech 10" S 69° E 28 lks.
Sugar 13" N 79° W 21½ lks.

1883: F. Hodgman, County Surveyor; found stone of resurvey in center of road and side stone West 50 lks. in line with fences East and West. Bored 3 ft. put in 1 ft. of stone and 2 ft. earthen post over with stone around.
Maple 4" N 69° E 61 lks. Burr Oak 12" N 16½° W 182 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1955: Wilkins and Wheaton found tile 16" deep, placed iron over tile
30" Maple N 50° E 46.50' 20" Maple N 45° W 29.0'
22" Black Walnut S 45° W 24.45' 26" Maple N 88° E 35.60'
30" Oak N 16½° W 119.0'

1971: Larry Watson, RLS #12447; L-1, P-155; found tile, set monument box over tile.
30" Maple N 50° E 46.50' 26" Maple N 33° E 35.60'
20" Maple N 45° W 29.00'

1996: Found tile in monument box (tile 22" deep, monument box 12" deep) 5.0'+/- West of centerline of road. Raised monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-11: Northeast corner Section 36, T 2 S, R 9 W; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with cross in top as set by F. Hodgman, County Surveyor in 1883 remonumentation survey. Placed 18" of Harrison monument and concrete in monument box over tile.
PK nail on North side 10" Maple N 62° E 42.45'
PK nail on Northeast side 36" Maple N 40° W 29.81'
PK nail on Southeast side 12" Twin Ash S 50° W 31.59'
PK nail on West side 12" Maple S 40° E 48.06'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 8-7-96