

SURVEY & REMONUMENTATION

1 SEP 14 1998

2 SECTION **LAND CORNER RECORDATION CERTIFICATE**

For corners in Comstock Township Filing Requirement of Act 74, Mich. P.A. 1970
Kalamazoo Located In: Corner Code #
 (County)

- | | | | | | |
|--------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>2S.</u> | R | <u>10W.</u> | <u>B-6</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 2 PAGE 290
 '98 MAR 26 PM 3 37
 CLERK - REGISTER
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on January 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4		3		2				
3												
4	7	6		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not placed by original Government Surveyors	<u>1910 - Ed Strong, C.S., "Wh. Oak 12" S. 30° W. 16 lks., Flat iron by Hodgman bisecting East and West, Fence South correct S. 1 lk." (For Survey of Leenhouts' Plat L. 3, Pg. 37)</u>	<u>1916 - Leenhouts' Plat is revised.</u>
<u>1870 - F. Hodgman, C.S., "Divided a(W¼ cor.) & d(E¼ cor.) proportionally and for center of Section. Planted iron bar and marked Y. Oak 5" N. 10° E. 3 lks., Wh. Oak 8" S. 15° W. 16 lks."</u>		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found flat iron bar 2¼" wide with notch cut in top, 2" below grade. Removed flat iron bar (20" long) and found 3 large stones around iron. Dug to depth of 3½" and found no additional evidence of corner. Location of iron matches 3 lot cors. in Revised Plat of Leenhouts' Plat and 2 lot corners in "Shield's Addition" (East of Leenhouts' Plat).

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 2-19-1998 *R. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found flat iron is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 30" Harrison Monument at position of found flat iron, Accessories:

- Nail in East side U. Pole N. 10° W. 60.07'
- Nail in Southerly side 36" Twin Cherry West 34.56'
- Nail in Southerly side 10" Oak N. 70° E. 9.48'
- Northeast corner house (#747) S. 45° W. 84.92'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 2/24/98