

'98 OCT 22 PM 1 22

LAND CORNER RECORDATION CERTIFICATE

For corners in COMSTOCK TWP Filing Requirement of Act 74, Mich. P.A. 1970
KALAMAZOO Located In: Corner Code #
 (County)

1. Public Land Survey	T	2S.	R	10W.	C-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

Timothy Johnson
 CLERK - REGISTER

LIBER 2 PAGE 360

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 6. IWM Job No. 31163-98

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Allen H. McMachen, in a field survey on May, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Robert Clark, Jr., D.S., Intersected North boundary 240 lks. East of post. Set post at intersection corner to Sections 5 and 6, Y. Oak 11" S. 44° W. 44 lks. dist., W. Oak 16" S. 50½° E. 77 lks. dist.

1885 - F. Hodgman, C.S., "Found stone set for corner. Set post with earthen under and stone over. Bearing trees of resurvey standing."
1901 - E. Strong, C.S., "Found tile good."

1864 - F. Stimson, C.S., Northeast corner of Section. Found both stumps. Planted stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron in monument box. Removed iron and box and found clay tile directly below surface iron. Top of tile is 3.7 feet below grade.

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

**RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 10-15-1998**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 30" Harrison Monument over found tile, Accessories:

- Nail & Tab in West side 16" Locust S. 15° E. 33.01'
- Nail & Tab in NW side 16" Maple N. 75° E. 81.85'
- "PK" Nail in West side of U. Pole S. 10° W. 30.33'
- Southerly corner of steel power tower (outside corner of metal at conc. pad) North 95.08'
- ½" iron in box (SE corner, Section 31, Richland Twp.) West 158.68'



Signed by Allen H. McMachen

Date 10/21/98

Surveyor's Michigan License No. 16935