

SURVEY & REMONUMENTATION

AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

'95 MAR 23 PM 4 09

For corners in **COMSTOCK TWP.**
KALAMAZOO
 (County)

Located In:

Corner Code #

James Young
 CLERK-REGISTER

1. Public Land Survey	T <u>2</u> S R <u>10</u> W	D-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 1 PG 1284

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Allen H. McMachen field survey on October 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - R. Clark, D.S., Set Quarter Section Post
 W. Oak 9" N. 02° E. 39 lks.
 W. Oak 18" S. 82° W. 10½ lks.

1885 - F. Hodgeman, C.S., Found Stone Quarter Post of former survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 1' below surface with 4"-6" Stones lying around it. Found Iron pipe 1.12' Northeasterly of found Tile.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

3/16/95 *R. S. S.*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Standard sleeve over existing Clay Tile. Accessories:

- Nail & Tab in E. Face 10" Hickory NORTH 20.10'
- Nail & Tab in N. Face 12" Basswood EAST 24.67'
- Nail & Tab in S. Face 12" Triple Cherry S. 45° W. 31.48'
- Nail & Tab in S. Face 12" Basswood N. 80° W. 27.44'

Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 3/22/95