

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Comstock Township Located In: _____ Corner Code # _____
Kalamazoo (County)

1. Public Land Survey	T	2S.	R	10W.	E-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

LIBER 2 PAGE 322
 98 OCT 12 PM 1 28
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 J. J. [Signature]
 CLERK - REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM JOB No. 31009

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3				●								
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Allen H. McMachen, in a field survey on March 28, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - Robert Clark, Jr., D.S., Set post. Cor. to Secs. 4, 5, 8, & 9. Y. Oak 18" S. 59° W. 20 lks. Y. Oak 20" N. 37° E. 18 lks..
- 1871 - F. Hodgman, C.S., "Found stake hole from stump roots of two witnesses. Planted stake and stone and marked Hickory 8" N. 57½° E. 80 lks.. Bl. Oak 10" N. 11° W. 181 lks.."
- 1885 - F. Hodgman, "Found stake & stone of resurvey. Bearing tree N.W. 181 lks. standing. Set post with stone beside." (Vol. 6, Pg. 458 indicates "post" as being the Section corner.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in mon. box. Removed iron, bored inside & found 2nd iron below the first. 2nd iron was 6" long and was sitting on top of the tile. Tile was 0.14' North & 0.05' West of 1st iron rod found.

SURVEY & REMONUMENTATION
 NOV 25 1998
 SECTION

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 4/16/98 R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over tile, Accessories:

- Nail & Tab in Easterly side of 52" Oak N. 11° W. 117.85'
- Nail & Tab in Southerly side 34" Pine N. 70° W. 91.36'
- Nail & Tab in Westerly side 18" Locust South 75.22'
- N.E. corner of garage S. 40° W. 113.77'



Signed by Allen H. McMachen

Date 4/28/98

Surveyor's Michigan License No. 16935