

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>2</u> S R <u>10</u> W	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

CLERK - REGISTER

James P. [Signature]

94 JAN 21 AM 8 56

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LIBER 1 PG 1093
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on December 29, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Established by United States Government Survey in 1825-Set Post

Wh. Oak 6" South 03°-W 21 Lks (13.86')
Wh. Oak 10" North 55°-E 40 Lks (26.40')

1864-F. Stimson, County Surveyor-Found government corner planted large piece of wood and iron-pieces of broken iron kettle.

1885-F. Hodgeman, County Surveyor-Found iron stake and stone of former survey at angle of fence. Set post with stone around.

Hickory 10" South 10°-E 15 1/2 Lks (10.23')
R. Oak 10" South 03°-W 24 1/2 Lks (16.17')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories not found.
Found solid clay tile with pieces of iron kettle.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/30/93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 West 1/4 Section 9, T. 2 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found solid clay tile with "X" on top with pieces of iron kettle as called for by 1885 Remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed monumentation sleeve over tile.

Bent Nai/Cap in Easterly side	10" Pine	North 40°-E	16.48'
PK Nail in Southerly side	24" W. Cherry	South 45°-W	16.24'
Nail/Cap in Southerly side	10" Pine	South	27.80'
Bent Nail/Cap in Northwest side	10" Pine	South 65°-W	13.13'

Signed by *Robert E. Snell*

Date 1-20-94

Surveyor's Michigan License No. 9734

