

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO

RECEIVED FOR RECORD
94 JAN 4 AM 9 02

For corners in

Kalamazoo
(County)
Comstock Twp.

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>2 S</u> R <u>10 W</u> | <u>F-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James E. Boynton
CLERK-REGISTER

LIBER **1** PG **1054**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James E. Boynton, in a field survey on Dec. 27, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter post ~~set~~ established by U.S. Government Deputy Surveyor John Mullet in 1826. Remonumentation by F. Hodgeman in 1885, set standard tile, witnesses: W.O. 16 S. 16 W. 49 1/2'; W.O. 8 N. 65 W. 129. Tile found in monument box by Ingersol, Watson, McMachen in 1972.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile in monument box from 1972 witnesses: P.P. S. 35° E. 28.20'; P.P. S. 20° E. 74.12'; R.R. tie post South 34.5'

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-30-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile and accepted as a careful and faithful perpetuation of the original corner. Set standard sleeve over tile in monument box, new witnesses: 12"x12" post South 30.98' to nail; P.P. N. 35° E. 28.29' to nail; guy pole S. 60° E. 73.94' to nail; 8"x8" post S. 50° W. 45.71' to nail.

Signed by James E. Boynton Date Dec. 29, 1993
Surveyor's Michigan License No. 29239