

LAND CORNER RECORDATION CERTIFICATE

For corners in COMSTOCK TWP Filing Requirement of Act 74, Mich. P.A. 1970
KALAMAZOO Located In: Corner Code #
 (County)

1. Public Land Survey	T	<u>2S.</u>	R	<u>10W.</u>	<u>F-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

LIBER PAGE 361

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '98 OCT 22 PM 1 22
 Clerk - Registrar
[Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 6. IWM Job No. 31331-98

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on July, 1998
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Robert Clark, Jr., D.S., Set quarter Section post, Wh. Wood 30" S. 75° E. 19 lks., Beech 7" S. 8° W. 13 lks..

1885 - F. Hodgman, C.S., "Found stake standing N. 8° W. 13 lks. from stump of bearing tree. Stump of Wh. Wood bearing tree tipped over S. 75° E. 19 lks.. Set post. Elm 2" North 8 lks., Elm 2" S. 75° E. 16 lks.."

1869 - F. Hodgman, C.S., "Quarter Section corner - Found stake from one witness and stump of the other. Drove new stake, put stone beside it and marked maple 18" S. 75° E. 27 lks. (shows measure on map from Southwest corner to South quarter corner at 40.09 ch.)."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile below concrete that was poured around 6½" dia. aluminum fence post. Tile is on North side of post.

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 10-15-1998
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile is accepted as a careful and faithful perpetuation of the position of the original corner. Broke out concrete above tile and placed Harrison Monument over tile. Top of tile was 14" below grade. Poured concrete back around Harrison Marker, Accessories:

- 60d Nail in West side 14" Maple N. 15° E. 50.58'
- 60d Nail in North side 16" Cherry N. 88° E. 18.97'
- 60d Nail in S.E. side 26" Oak N. 50° W. 15.76'
- 60d Nail in S.W. side 12" Maple S. 43° E. 57.81'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 10/21/98