



LC-000094  
Page: 1 of 1  
12/20/1999 10:07A  
Sk-2 Pg-547

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMSTOCK TWP  
KALAMAZOO  
(County)

Located in: Corner Code #  
T 2S. R 10W. G-1  
T      R            
T      R            
T      R            
T      R            
S      T      R       
S      T      R       
S      T      R       
S      T      R     

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

SURVEY & REMONUMENTATION  
FEB 08 2000  
SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. IWM Job No. 32282

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Allen H. McMachen, in a field survey on November, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - Robert Clark Jr., D.S., Intersected North boundary (base line) 148 lks. West of 1/4 Section post. Set post at intersection corner to Sections 3 and 4, Y. Oak 30" S. 10° W. 30 lks., Wh. Oak 18" N. 55° E. 95 lks..
- 1885 - F. Hodgman, C.S., "Found stake with brick around in line with fence South. No witness trees. Set post with brick around Y. Oak 6" N. 01° W. 41 lks., Hickory 6" S. 06° E. 37 lks..
- 1894 - Ed Strong, C.S., "Tile found".
- 1938 - Wilkins & Wheaton, "Tile"
- 1940 - Wilkins & Wheaton, NE corner - marker not defined
- 1967 - Ingersoll, Watson & McMachen, Inc., Found iron

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
11-18-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod. Dug a 2' X 2' X 4' deep hole and found larger sections of brick directly below surface iron and 3 feet below grade but did not recover clay tile. Brick was in a layer of virgin sand. The roadway in this area appears to have been cut 2'-3' judging from surrounding ground. Measured from position of surface iron West 86.58' (G.L.O. = 86.46') to a found tile (ratified) at the Southeast corner of Section 33, Richland Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found iron rod above broken brick is accepted as the best available evidence of the position of the original corner. Placed a 30" Harrison Monument with brick around base in place of found iron rod with monument box over, Accessories:

- Iron rod placed N. 60° E. 24.71'
- Iron rod placed N. 60° W. 42.54'
- Iron rod placed S. 70° W. 42.46'
- Iron rod placed S. 45° E. 24.20'



Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 12/17/99