

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
Clerk - Register

For corners in

Kalamazoo Located In: _____ Corner Code# _____
(County)
Comstock Twp.

| | | |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey | T <u>2S</u> R <u>10W</u> | <u>G3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on October 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Established by U.S. Deputy Surveyor Robert Clark, Jr.:
W. Oak 24" S 6 E 39 Lks. W. Oak 20" N 88 W 73 Lks.

1871 F. Hodgman - "Sec. Corner. Planted stake iron & stone from roots of two witnesses and marked". Bk. Oak 5 N 74 1/2 E 115
Y. Oak N 46 E 48 Y. Oak 4 S 6 E 193 1/2

1875 F. Hodgeman - "Found stake stone and iron of resurvey. Set post". Hick. 8" N 44 E 54 Lks. Wh. Oak 10" S 79 W 136 1/2 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found 1/2" dia. 24" long rod 3.5' ± below road surface. Fnd. clay tile directly below rod at depth of 5' ± below road surface. Road to receive 3' ± more fill during 1998 reconstruction. Left tile in place

Note: Found 8"x8"x? Stone lying next to and southeast of tile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3, Northeast Corner Section 9, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on November 19, 1998. Position of the tile is accepted as a carefull and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over tile.

Witness Ties:

- P.K. Nail in P.P. S 60 E 66.07'
- P.K. Nail in P.P. S 40 W 58.71'
- P.K. Nail in 15" Hickory N 20 E 28.69'
- P.K. Nail in 18" Maple N 50 W 54.79'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

11/19/98

[Handwritten Signature]



Signed by *[Handwritten Signature]*
Surveyor's Michigan License No. 38116

Date 12/08/98
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995

SURVEY &
REMONUMENTATION

FEB 08 1999

SECTION