

SURVEY & REMONUMENTATION

SEP 14 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 JAN 15 PM 3 20
Annexed Record
CLERK - REGISTER

For corners in SECTION

Kalamazoo (County)	Located In:	Corner Code#
Comstock Township		
1. Public Land Survey	T 2S R 10W	G-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 2 PAGE 282

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary D. Hahn, in a field survey on May 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Southeast corner established by US Deputy Surveyor Robert Clark, Jr.
Witness ties: 9" W. Oak S 12 deg. W 67 lks.
6" W. Oak N 71 deg. E 27 lks.

1885 - F. Hodgman: "Found iron post with another under. Set post w/iron and brick around." Cherry 4" dia. North 27 deg. E ?, Basswood 2" South 46 1/2 deg. W ?

KCRC Witness tie notes: Found iron 2" below surface and tile 2' below iron
(W) Bass 16" S 45 deg. W 51.9 feet
(W) Hickory S 75 deg. W 92.22 feet
(W) Maple 18" N 60 deg. W 69.14 feet
(W) Elm 18" N 30 deg. E 82.8 feet
(W) Power Pole S 50 deg. E 52.15 feet

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-19-1997 *R.E.S.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found 1/2 inch iron rod in monument box below asphalt. Found 1 inch pinch pipe 2.6 feet below road surface and surrounded by four 8" dia. stones. Removed irons and stones. Found tile with "X" 4.2 feet below road surface. Tile, pipe and rod all in same location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5, Northwest corner Section 15, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on June 19, 1997. Position of tile is accepted as a careful and faithful perpetuation of the position of the original corner. Set a 20" Harrison Monument in a mon. box over tile.

Witness ties: Set Mag. nail in power-pole N 70 deg. W 51.51 feet
Set Mag. nail in 29" hickory S 75 deg. W 93.39 feet
Set Mag. nail in power pole S 50 deg. E 52.34 feet
Set Mag. nail in 27" Maple N 75 deg. W 69.65 feet

Signed by *Gary D. Hahn* Date 12/19/97

Surveyor's Michigan License No. 38116

