

SURVEY & REMONUMENTATION

OCT 06 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 182

CLERK - REGISTER

J. J. [Signature]

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 AUG 21 PM 1 50

For corners in **COMMISSION**

KALAMAZOO (County)	Located In:	Corner Code #
COMSTOCK TWP.		
1. Public Land Survey	T <u>2S</u> R <u>10W</u>	<u>G-7</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary D. Hahn, in a field survey on June 14, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 Southwest corner established by U.S. Deputy Surveyor Robert Clark, Jr.
 Accessories: 10" W. Oak N89½ E 301ks. 9" W. Oak N72 W 37 lks.
- 1885 F. Hodgman "End. stake iron stone & brick set for corner & B. tree of resurvey standing. Set post with iron & brick under & stone around, 55 lks. from S. rail of M.C.R.R."
- 1870 F. Hodgman "End. corner of sec. 15, 16, 21, & 22 by digging. Planted iron bar & stone. S. rail of M.C.R.R. north 55 links"
- 1935 Mich. State Hwy. Dept. Fed. Aid Project No. 21 (plans) "Chiseled "X" in Pav't." N. edge of pav't. N. 0.22' S. edge of S. Rail M.C.R.R. N. 36.3' M.C.R.R. crossing sign ? ?
 ? oak S46 E 39.77' S. edge of pav't. S. 19.85' 16" Red Oak S56 ? 42.37' At station 89+21.62'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. No evidence of corner found in asphalt road surface. Dug a 3'x3' hole through 6" of asphalt to the old road concrete slab. Concrete was very crumbled so no "X" was found. Removed concrete slab and found a tile with an "x" on top in an upright position. Tile is 2.4' below surface of road. Found no evidence of iron bar, stone, or brick.

Note: Tile is 2649.96' West of S1/4 post Sec. 15

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 6-19-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7, Southwest corner Section 15, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on June 19, 1997. Position of the tile is accepted as a careful and faithful perpetuation of the position of the original corner. Set a 20" Harrison Monument in a Monument Box directly over tile.

- S. edge of South rail North 36.08'
- N. edge of Conc. driveway South 41.22'
- Set P.K. nail in P.P. N45 E 29.94'
- Set P.K. nail in P.P. S30 E 65.59'



Signed by *[Signature]*

Date 8-20-97

Surveyor's Michigan License No. 38116