

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in COMSTOCK TWP Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
KALAMAZOO (County)

1. Public Land Survey	T	<u>2S.</u>	R	<u>10W.</u>	<u>G-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

LIBER 2 PAGE 362

CLERK - REGISTER

98 OCT 22 PM 1:22

REGISTER OF DEEDS STAMP & FILE NUMBER

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

6. IWM Job No. 31331-98

I, Allen H. McMachen, in a field survey on September, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1827 - Robert Clark, Jr., D.S., Set post corner to Sections 27, 28, 33 and 34, Beech 12" N. 80° W. 10 lks., Beech 6" N. 61° E. 7 lks..
- 1885 - F. Hodgman, C.S., "Found iron stake and bearing trees standing correct. Set post with iron under and stone around."
- 1870 - F. Hodgman, C.S., "New iron stake for corner. Original witnesses standing, found another stake and stone 3 lks. South."
- 1903 - Ed Strong, C.S., "Found tile."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found clay tile 5.8 feet West of North-South fence. A 1" diameter iron rod was found on South side of tile, lying against tile. Found iron bar Northeasterly 1.94 feet from tile. Tile was found 16" below grade.

**SURVEY &  
REMONUMENTATION**

NOV 25 1998

SECTION

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
10-15-1998

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve over tile, Accessories:

- 60d Nail in East side 20" Ash S. 02° E. 27.75'
- 60d Nail in West side 28" Beech S. 50° E. 15.79'
- 60d Nail in East side 18" Maple N. 20° E. 12.17'
- 60d Nail in North side 20" Basswood N. 70° W. 18.04'



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 10/21/98