

SURVEY & REMONUMENTATION

7 FEB 26 1998

LIBER PAGE 271

2 SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code#
(County)		
Comstock Township		
1. Public Land Survey	T <u>2S</u> R <u>10W</u>	<u>H-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 23 PM 12 57
J. D. Hahn
CLERK - REGISTER

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on May 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6/19/97 [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

1826 - North Quarter post established by US Deputy Surveyor Robert Clark, Jr.

Witness ties: W. Oak 12" N 7 deg. E 14 lks.
W. Oak 9" S 74 1/2 deg. E 53 lks.

1885 - F. Hodgman "Corner lost - set post in line midway between the section corners east and west"

Witness ties: Y. Oak 14" N 41 1/2 deg. E 34 lks.
Hickory 2" S 37 3/4 deg. W 57 lks.

Date ? - KCRC Witness tie notes: 1 inch pipe (Acro), Power pole (no. 515) 44 feet south, Power pole N 50 deg. W 83.0 feet, 8" Maple S 60 deg. W 66.6 feet.
2 feet south of north edge of pvm't.

1963 - (Gove witness ties) Power pole No. 515 S 44.06 feet
Power pole N 60 deg. W 82.85 feet
10" Hickory S 70 deg. W 66.44 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found 1 inch dia. 36" long iron rod in pvm't. Removed iron and found tile 23" below road surface. Tile is 0.52 feet south and 0.90 feet west of 1 inch rod. Tile is 0.07 feet south and 0.63 feet east of bi-section of corners G-5 and I-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5, North Quarter Post Section 15, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on June 19, 1997. Position of tile is accepted as a careful and faithful perpetuation of the position of the previously reestablished position of the original corner. Set 20" Harrison Monument in Mon. box over the tile.

Witness ties: Set Mag. nail in power pole South 44.12 feet
Set Mag. nail in power pole N 60 deg. W 82.71 feet
Set Mag. nail in 19" Hickory S 70 deg. W 65.30 feet
Set 1/2 inch rebar N 45 deg. E 30.60 feet

Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 12/22/97

