

**SURVEY &  
REMONUMENTATION**

7  
2  
SEP 14 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

|                                    |                          |              |
|------------------------------------|--------------------------|--------------|
| <u>Kalamazoo</u>                   | Located In:              | Corner Code# |
| (County)                           |                          |              |
| Comstock Township                  |                          |              |
| 1. Public Land Survey              | T <u>2S</u> R <u>10W</u> | <u>H-6</u>   |
|                                    | T _____ R _____          | _____        |
|                                    | T _____ R _____          | _____        |
|                                    | T _____ R _____          | _____        |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____        |
|                                    | S _____ T _____ R _____  | _____        |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____        |
|                                    | S _____ T _____ R _____  | _____        |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary D. Hahn, in a field survey on June 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

This corner not established during original Government Land Office Survey.  
1897 - E. Strong: "Found iron stake pulled up - replaced it the same hole"  
1939 +/- - Consumers Power Company survey: "Found 2" x 1/4" flat iron at intersection of fences and center section 15. Irons set by Strong".  
12" W. Oak SW 9.5 feet  
8" Ash S 7.8 feet  
Date ? - Gove Associates witness ties: "Northerly knob on 3/4" x 3" iron".  
24" Oak S 70 deg. W 9.86 feet  
8" Oak S 10 deg. W 22.60 feet  
8" Cherry S 85 deg. E 19.80 feet

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
6-19-1997 *R.E.S.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 2 1/2" x 30" long steel bar with notch on top. Found barbed wire strands running east and west laying down or buried. Found 6" x 7" X 10" stone lying against the bar to the west. Bar is approximately 0.6 feet north and 1.3 feet east of intersection of quarter lines as established by holding tiled locations of the north quarter post, east quarter post and south quarter post and the previously ratified Harrison Monument at the west quarter post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-6, Center of Section 15, Town 2 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on June 19, 1997. This position not established by original government surveyors. This monument "the northerly knob of the found iron bar" is accepted as the best available evidence of the position of the corner. Removed iron bar and set 30" Harrison Monument in the location of the northerly knob of the iron bar.  
Witness ties: Found nail with tab in 6" Ash South 22.55 feet  
Set PK nail in 4" Ash N 32 deg. E 8.62 feet  
Set PK nail in 16" Hickory S 85 deg. E 12.97 feet  
Set PK nail in 30" Hickory S 70 deg. W 9.99 feet

Signed by *Gary D. Hahn* Date 12/22/97  
Surveyor's Michigan License No. 38116

